

Nu-Wave Pools pricing guide

DELIVERY – (ACCORDING TO WIDTH) F.O.B.

-SPA SHELLS (EXCEPT MONTREAL AND VANCOUVER)	600.00
-UP TO 12' WIDE	1,600.00
-UP TO 14' WIDE	1,800.00
-UP TO 16' WIDE	2,000.00

INSTALLATION–

-SMALL POOLS UP TO 12' WIDE AND 25' LONG	5,000.00
-MED. POOLS UP TO 14' WIDE AND OR 32' LONG	5,500.00
-LRG. POOLS UP TO 16' WIDE AND OR 40' LONG	6,000.00
-EXTRA LRG AND OR LONGER THAN 40'	6,500.00

***ALL 8' POOLS + 500.00 ADDITIONAL TO SIZED PRICING**

*FILL REMOVAL ABOVE VOLUME OF SHELL SIZE FIGURED AT 100.00 PER 6 YRD LOAD

STRUCTURAL RIB REINFORCEMENT– FOR BAD SOIL CONDITIONS

OR OUT OF GROUND INSTALLATIONS AND PRICED PER JOB AND SIZE OF SHELL

-OUT OF GROUND INSTALLATIONS UP TO 18"	1,000.00 – 2,000.00
-OUT OF GROUND INSTALLATIONS UP TO 3'	2,000.00 – 4,000.00
-TOTAL OUT OF GROUND INSTALLATIONS	4,000.00 AND UP

DEWATERING SYSTEMS– STONEBED AND OR WELLPOINTS TO CONTROL

GROUND OR SURFACE WATER DISPLACEMENT AND DRAINAGE

-BASIC DRY HOLE FOR FUTURE DRAINAGE OF CAPTURED SURFACE WATER OR POTENTIAL HIGH WATER TABLE	500.00 – 750.00
-WET HOLE, CLAY, OR MARSH MUCK REQUIRING STONEBED, PUMPS AND SOME WELL POINTS.	1,000.00 – 1,500.00
-GROUND WATER REQUIRING EXTENSIVE WELL POINT SYSTEM OF 8 OR MORE TO PROPERLY DEWATER GROUND	2,000.00 AND UP

PILING AND ENGINEERING FOR PILING–

-FOR ANCHORING OF POOLS ALONG COASTAL TOWNS REQUIRED BY SOME ZONING DEPARTMENTS	2,500.00
-FOR STRUCTURAL PURPOSES TO BE CAPPED WITH CONCRETE REQUIRED BY SOME TOWNSHIP BUILDING DEPARTMENTS DO TO SOIL CONDITIONS	PRICED PER JOB

TIGHT WORKING CONDITIONS–

-THE USE OF SMALL EQUIPMENT OR ADDITIONAL LABOR TO ACCOMMODATE LIMITED ACCESS OR ROOM TO WORK	1,500.00
---	----------

JOB PREPERATION–

-ANY ADDITIONAL WORK SUCH AS REMOVAL OF BRUSH, TREES, STUMPS, MOVING SHEDS, OR EXISTING DECK OR CONCRETE REMOVAL ETC...	PRICED PER JOB
---	----------------

CRANE OR BARGE–

-LIMITED SPACE OR ACCESS RESULTING IN UTILIZING SPECIAL MEANS OF LIFTING POOL/ SPA SHELL INTO BACKYARD OR HOLE.	PRICED PER JOB
---	----------------